3	51	Supplying and fixing single phase preventer complete as per specfication & as per direction of Engineer-in-charge	Each	40.00	735.0	Rupees Hundred Five
	52	Supplying fixing and wireing 0 to 600 volts 96 X 96mm AC Voltmeter complete as per specfication & as per direction of Engineer-in-charge	Each	20.00	430.0	Rupees Hundred
40	53	Supplying fixing and wireing 0 to 100 amps direct reading AC analog ammeter complete as per specfication & as per direction of Engineer-in-charge	Each	20.00	495.0	Rupees Hundred Five
	54	Supplying fixing and wireing rotary sector switch suitable for ammeter complete as per specfication & as per direction of Engineer-in-charge	Each	20.00	430.0	Rupees Hundred Only
	55	Supplying fixing and wiring rotary sector switch suitable for voltmeter complete as per specfication & as per direction of Engineer-in-charge	Each	20.00	245.0	Rupees Hundred Five Only
	56	Supplying and fixing for LED type panel board indicating lamp with 220 V AC 50 Hz 12/24v DC a) group A) complete as per specfication & as per direction of Engineer-in-charge	Each	35.00	430.0	Rupees Four Hundred Only
	57	Supplying and fixing of 4 pole power contractor complete as per specfication & as per direction of Engineer-in-charge	Each	40.00	925.0	Rupees Nine Hundred Five Only
	58	Providing and fixing in position 50mm nominal bore non-return valve horizontal type of approved make including cost of all materials labour and HOM of equipments with all leads complete as per specfication & as per direction of Engineer-in-charge	No	40.00	1051.0	Rupees One Thousand Fifty One Only
	59	Supplying and fixing 50mm GL union complete as per specfication & as per direction of Engineer-in-charge	No	60.00	223.7	Rupees Two Hundred Three and Seventy Only
	60	Supplying and fixing 50mm GL Elbow complete as per specfication & as per direction of Engineer-in-charge	No	120.00	111.8	Rupees One Hundred and Eighty Only
	61	Supplying and fixing 50mm GL Nipple complete as per specfication & as per direction of Engineer-in-charge	No	120.00	104.3	Rupees One Hundred and Thirty Only

Signature of the Contractor

Executive Engineer
Dasrahalli Divsion
BBMP

38	Lifting of submersible pump set	Each	80.00	770.0	
39	Labour charges (Over hauling only)	Each	80.00	550.0	
40	Supply and drawing 3 core flabr PVD sheathed submersible pump cable manufacture with electrolytic grade copper with flexible copper conductor confirming to calbe 3 class 5 of IS 8130 - 1984 and altes amendments of IS 694 / 1990 and virgin grade PVC insulation and sheathed suitable for working volgrage upto 1100 volts complete as per specfication & as per direction of Engineer-in-charge	Rmt	3000.00	159.5	
41	Fabricating supplying and mounting MS box made out 14 SWG suitable for floor/ wall mounting fully weather proof with provision for better hear dissipation provided with hinged front cover equipped with tamper proof locking arrangementw with suitable size clamps with necessary calbe entry pipw with gland box should be finished with 2 coats of red oxide primer paint and finally finished with approved color enameled metal paint etc.,complete as per specfication & as per direction of Engineer-in-charge	Sqm	616000.00	0.33	Thirty Paise
42	Supplying and fixing angle iron frame work fabricated out of MS angle iron and MS flat bolts, washers etc and painted with 2 coats of red oxide and then two coats of approved paint 40X40X6mm 4X50 Nos	No	50.00	231.0	
43	Supplying and fixing polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapers incerted wooden plugs screws etc F) 20" X20"X2.5" complete as per specfication & as per direction of Engineer-in-charge	Each	50.00	285.0	
44	Supplying and fixing miniature circuit breaker on existing MCB distribution board using necessary fixing materials and wiring complete as per required 40 to 63 amps	No	50.00	1897.5	

Signature of the Contractor

9	Guide vane complete as per specfication & as per direction of Engineer-in-charge	No	1200.00	192.5	Rupees One Hundred Ninety Two and Fifty Paise Only
10	Impeller (shell moulded with aluminium and bronze) complete as per specfication & as per direction of Engineer-in-charge	No	1200.00	264.0	Rupees Two Hundred Sixty Four Only
11	Discharge outlet (D.O.) bearing D.O. steel bush complete as per specfication & as per direction of Engineer-in-charge	No	80.00	522.5	Rupees Five Hundred Twenty Two and Fifty Paise Only
12	D.O.bearing complete as per specfication & as per direction of Engineer-in-charge	No	200.00	93.5	Rupees Ninety Three and Fifty Paise Only
13	Steel bearing bush (D.O.Steel Bush) complete as per specfication & as per direction of Engineer-in-charge	No	200.00	176.0	Rupees One Hundred Seventy Six Only
14	Allen screw complete as per specfication & as per direction of Engineer-in-charge	No	160.00	77.0	Rupees Seventy Seven Only
15	Pump shoft made out of stainless steel center less ground with key way (upto 8 stages) + R. 40/- Extra 20 stages complete as per specfication & as per direction of Engineer-in-charge	No	60.00	660.0	Rupees Six Hundred Sixty Only
16	Pump Key complete as per specfication & as per direction of Engineer-in-charge	No	80.00	121.0	Rupees One Hundred Twenty One Only
17	Pump couping (stainless steel) complete as per specfication & as per direction of Engineer-in-charge	No	80.00	341.0	Rupees Three Hundred Forty One Only
18	Non return valve (NRV) assembly complete. Rubber 'O' ring complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	572.0	Rupees Five Hundred Seventy Two Only
19	Cable guard complete as per specfication & as per direction of Engineer-in-charge	Each	160.00	165.0	Rupees One Hundred Sixty Five Only
20	Strainer complete as per specfication & as per direction of Engineer-in-charge	Each	50.00	192.5	Rupees One Hundred Ninety Two and Fifty Paise Only
21	Brass filter complete as per specfication & as per direction of Engineer-in-charge	Each	50.00	121.0	Rupees One Hundred Twenty One Only
22	Labour charges (over hauling only) Per Job complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	550.0	Rupees Five Hundred Fifty Only

Signature of the Contractor

Executive Engineer,
Dasrahalli Divsion,
BBMP

	Above 4 HP below 5 HP startor (with one year guarantee)	Each	20.00	5940.0	Rupees Five Thousand Nine Hundred Forty Only
	Above 4 HP below 5 HP Rotor (with one year gurantee)	Each	20.00	4400.0	Rupees Four Thousand Four Hundred Only
5	Upper flange complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	330.0	Rupees Three Hundred Thirty Only
6	Lower housing complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	539.0	Rupees Five Hundred Thirty Nine Only
27	Lower flange complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	407.0	Rupees Four Hundred Seven Only
28	Lock ring complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	88.0	Rupees Eighty Eight Only
29	Carbon housing complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	407.0	Rupees Four Hundred Seven Only
30	Thrust bearing block assembly with segment bearing pad complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	550.0	Rupees Five Hundred Fifty Only
31	Tip carbon complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	1760.0	Rupees One Thousand Seven Hundred Sixty Only
32	Studs and nuts complete as per specfication & as per direction of Engineer-in-charge	Each	200.00	88.0	Rupees Eighty Eight Only
33	Bearing (gunmetal) centrifugal Cast aluminium bronze, bearing bush complete as per specfication & as per direction of Engineer-in-charge	Each	140.00	407.0	Rupees Four Hundred Seven Only
34	Circlips complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	49.5	Rupees Forty Nine and Fifty Paise Only
35	Motor base with pin complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	407.0	Rupees Four Hundred Seven Only
36	Transportion of pumping Machineres complete as per specfication & as per direction of Engineer-in-charge	Each	80.00	605.0	Rupees Six Hundred Five Only
37	Re-erection charges of pumping machineries including overhauling and painting	Each	80.00	1100.0	Rupees One Thousand One Hundred Only

Executive Engineer,
Dasrahalli Divsion,
BBMP

Signature of the Contractor

	Supplying and fixing one of the fuse cutouts having porcelain base approved quality on the existing wooden block and wiring complete	No	180.00	231.0	Rupees Two Hundred Thirty One Only
46	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150mm dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (wet type) squirrel cage submercible induction motor suitable for operation of 3Ph, 50Hz., 380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 12.5. HP 25 stage complete as per specfication & as per direction of Engineer-in-charge	No	5.00	63400.0	Rupees Sixty Three Thousand Four Hundred Only
47	Supplying of LTUG cable having aluminium conductor PVC insulated sheathed galvanized steel wire/ steel tape armored calbe with PVC outer sheathing 1.1 KV class conforming IS 1554-PVC cable.	Rmt	200.00	165.0	Rupees One Hundred Sixty Five Only
48	Digging of trench of 0.6m deep X 0.50 wide refilling the trence to the required ground level and consolidating etc complete. In ordinary soil complete as per specfication & as per direction of Engineer-in-charge	Cum	90.00	55.0	Rupees Fifty Five Only
49	Labour charges for laying 1.1 KV class UG cable when supplied departmentally/agency in existing trench GI pipe/stoneware pipe/on wall/on pole as required.	Rmt	200.00	5.5	Rupees Five and Fifty Paise Only
50	Supplying fully automatic star - delta starter unit push button type with suitable wires 3 contractor, one adjustable thermal timer mounted on a common base plate heeld in steel enclosure for use on 400/400 volts 3 phase and wired after fixing to the existing wooden board for motor. complete as per specfication & as per direction of Engineer-in-charge	Each	10.00	6583.0	Rupees Six Thousand Five Hundred Eighty Three Only

Executive Engineer,
Dasarahalli Divsion,
BBMP

Signature of the Contractor